

**SkyCalc: Skylight Design Assistant - Graphic Results**

**Company Name:** CLIENTE GREENFLEX-OD-CV-05-2012  
**Project Description:** THD - OD-CV-05-2012

Dome Skylight Effective Aperture = 2.26%, Skylight to Floor Ratio (SFR) = 3.89%

**Average daylight lux (LUX)**

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Jan	0	0	0	0	0	0	0	14	99	190	286	353	383	401	364	287	174	55	2	0	0	0	0	0
Feb	0	0	0	0	0	0	0	20	117	216	296	485	414	428	407	320	214	86	9	0	0	0	0	0
Mar	0	0	0	0	0	0	0	43	157	272	387	554	444	431	420	342	231	116	11	0	0	0	0	0
Apr	0	0	0	0	0	0	7	83	200	302	442	450	360	435	432	330	227	103	12	0	0	0	0	0
May	0	0	0	0	0	0	14	101	210	284	398	373	340	403	466	350	243	117	21	0	0	0	0	0
Jun	0	0	0	0	0	0	16	98	219	347	430	387	317	383	420	338	238	117	28	0	0	0	0	0
Jul	0	0	0	0	0	0	9	83	193	322	424	408	308	386	432	318	213	112	29	0	0	0	0	0
Aug	0	0	0	0	0	0	5	66	189	339	435	430	336	389	455	342	213	99	18	0	0	0	0	0
Sep	0	0	0	0	0	0	4	69	187	310	378	425	414	450	420	322	206	83	5	0	0	0	0	0
Oct	0	0	0	0	0	0	2	57	171	287	374	469	452	420	370	257	143	36	0	0	0	0	0	0
Nov	0	0	0	0	0	0	0	38	139	238	313	446	398	368	309	213	112	20	0	0	0	0	0	0
Dec	0	0	0	0	0	0	0	18	96	184	270	414	316	324	299	219	124	30	0	0	0	0	0	0

Design Illuminance = 300 LUX

Location = Córdoba, Veracruz

